




Changing How We Build Highways and Bridges in America

Highways for LIFE


Accelerating innovation for the American driving experience





Byron N. Lord
Program Coordinator
Highways for LIFE



More cars and trucks Old highways and bridges



Too many crashes and injuries



What if we built :

- Faster?
- With less congestion?
- With better safety and quality?
- At lower cost?



What's different?

- Setting performance goals
- Seeking the best solutions



Demonstration Project Performance Goals

- Focus on user
- Set at a high level
- Define end results
- Significantly improve how we build highways



Highways for LIFE

- Long Lasting**
- Innovative**
- Fast Construction**
- Efficient and Safe**



Highways for LIFE

Accelerate innovation by:

- Incentive Funding for Demonstration Projects
- Technology Transfer
- Technology Partnerships
- Communication



Vanguard Technologies

- Prefabricated Bridge Elements and Systems
- Road Safety Audits
- Making Work Zones Work Better
- Precast Concrete Pavement Systems
- The Safety Edge



Highways for LIFE

Demonstration Projects

- Incentive Funding (\$1 million)
- Performance goals for safety, quality, construction congestion and user satisfaction
- Innovations to achieve goals




Highways for LIFE Demonstration Projects

One-day workshop *Building a successful HfL application*

Seeking the Best Solutions

- ✓ Performance Goals
- ✓ Innovations to achieve goals
- ✓ Opportunity for “out of box” thinking



Highways for LIFE
Technology Transfer

Accelerate innovation through:

- Technology transfer
- Technology partnerships

The slide features a background image of a highway interchange with a person in the foreground. The text is overlaid on a white background.



Technology Transfer

- Workshops/open-houses/showcases
- Videoconferences
- Webinars (NHI Innovations)
- Toolkit DVD's (PBES, HfL)
- Marketing Plans
- Peer to Peer exchanges
- Technical support and assistance

The slide features a background image of a highway interchange with people in the foreground. The text is overlaid on a white background.



Highways for LIFE
Technology Transfer

Two-day workshop

Performance Contracting

- ✓ Performance Contracting Framework
- ✓ Performance Goals
- ✓ Preparing your contract

The slide features a background image of a highway interchange with people in the foreground. The text is overlaid on a white background.



Highways for LIFE
Technology Transfer

Two-day workshop

Accelerated Bridge Construction

- ✓ Customized to meet States needs
- ✓ Technical support and assistance

The slide features a background image of a highway interchange with people in the foreground. The text is overlaid on a white background.



Highways for LIFE
Technology Transfer

Two-day Training course

**NHI Training Course:
Accelerating the Adoption of Innovation**

For additional information:
Kathleen.Bergeron@dot.gov

The slide features a background image of a highway interchange with people in the foreground. The text is overlaid on a white background.



Technology Partnerships

“Financial impetus to accelerate commercialization of promising innovations.”


- 7 Projects Awarded
- Award range \$200-500k
- 3rd solicitation to expand outreach for FY-2009 this summer

The slide features a background image of a highway interchange with people in the foreground. The text is overlaid on a white background.

Communications



- **Innovator** newsletter
- **Articles and presentations**
- **Open houses and workshops**
- **www.fhwa.dot.gov/hfl**



Maryland 2007



Innovations:

- Full road closure
- Precast, prestressed bridge elements
- Integral abutments
- Innovative contracting

Benefits:

- Project complete within 60 days versus 1 year





Virginia 2007

Innovations:

- Precast concrete pavement systems (both prestressed and jointed systems)
- Innovative contracting
- Elaborate MOT technologies (ITS)
- I-66 & US 50 Ramp

Benefits:

- 75% reduction in construction impacts to traffic




California 2007

Innovations:

- Precast concrete pavement systems
- CA4PRS Software
- Dynameq Software

Benefits:

- Longer lasting pavement
- Optimize construction sequence, reduce impact to users





Utah 2007

Innovations:

- Total prefab bridge
- Self propelled modular transporter
- Construction manager contractor
- Work zone traffic technologies
- Silica fume concrete deck

Benefits: Traffic was interrupted for 48 hours only





Highways for LIFE
Accelerating innovation for the American driving experience

Questions?

U.S. Department of Transportation
Federal Highway
Administration



Highways for LIFE
Accelerating innovation for the American driving experience

Contact your Division Office or
www.fhwa.dot.gov/hfl

U.S. Department of Transportation
Federal Highway
Administration

Federal Highway Administration Precast Concrete Pavement Program



Suneel Vanikar, Office of Pavement Technology
VDOT Highways for LIFE Showcase
September 22-23, 2009



Why Precast Concrete?

- Proven construction technique for bridges, commercial buildings and parking structures.
- High-performance durable concrete from controlled manufacturing facilities.



Maintenance of Traffic

- Expedited Construction
- Nighttime and Weekend Hours



FHWA's Precast Concrete Pavement Program

Supports the advancement of precast concrete pavement applications through research, technology transfer, innovation, and increased product knowledge.

Precast Concrete Pavement –

*Vision for Implementation
Rapid repair, rehabilitation, and reconstruction of asphalt and portland cement concrete (PCC) pavements on high-volume roadways.*

Overview of FHWA Activities

- 2000 – Feasibility Study, Univ. of TX/Austin
- 2002 – Pilot Project, Georgetown, TX
- 2004 – Demonstration, El Monte, CA
- 2006 – Demonstration, Sikeston, MO
- 2006 – Demonstration, Sheldon, IA
- 2009 – Demonstration, Newark, DE
- 2009 – Highways for LIFE, Fairfax, VA
- Current – Design & Construction Support
- Current – Guidance Document Development

AASHTO Technology Implementation Group

June 2008 – Documents completed:

- ◆ *“Generic Specification for Precast Concrete Pavement System Approval”*
- ◆ *“Guidance & Considerations for Design of Precast Concrete Pavement Systems”*
- ◆ *“Generic Specification for Fabricating & Constructing Precast Concrete Pavement Systems”*

Strategic Highway Research Program (SHRP 2) Project R05, Modular Pavement Technology

- ◆ *Focus on tools that public agencies can use for design, construction, installation, maintenance, and evaluation of modular pavement systems.*
- ◆ *Phase I Report, February 2009 – Review of modular pavement systems; agency and industry experience; identification of successful strategies, promising technologies, and future needs.*

Technical Organization Activities

- ◆ *American Concrete Institute – Document summarizing technologies and case studies.*
- ◆ *American Concrete Pavement Association – Creating paving industry awareness.*
- ◆ *Precast/Prestressed Concrete Institute – Guidance document development.*
- ◆ *National Precast Concrete Association – Guidance document development.*

Developments Outside the U.S.A.

- ◆ *France – Hexagonal shaped precast concrete panels used for “removable urban pavement” (RUP) to facilitate access to underground utilities and other maintenance operations.*
- ◆ *Indonesia – Currently embarked upon the design and construction of a 22-mile precast prestressed concrete pavement that will be the longest in the world.*

Developments Outside the U.S.A.

- ◆ *Japan – Applications of precast pavement include bases for high speed rail; airport aprons and runways; and roadways in tunnels, at intersections, and other locations.*
- ◆ *The Netherlands – A precast concrete structural system, ModieSlab, can have a relatively thin and durable top layer for noise reduction or a porous surface can be incorporated to reduce tire-pavement noise and to diminish wet weather spray effects.*

Developments Outside the U.S.A.

- ◆ *Russia – A long history of precast pavement includes: highway and airport applications; temporary roads in permafrost environments; heavy industrial traffic applications; as well as urban traffic applications in Moscow.*

Future Activities

- ◆ *Further development and refinements of precast concrete pavement systems.*
- ◆ *SCAN – 2011 with AASHTO and NCHRP.*
- ◆ *Major projects – Planning, design, and construction.*
- ◆ *Specifications, guidance documents, and incorporation in routine practice.*


Questions ?

Further information –

- ◆ *Suneel Vanikar*
suneel.vanikar@dot.gov
Phone: 202-366-0120
- ◆ *Sam Tyson*
sam.tyson@dot.gov
Phone: 202-366-1326

National Overview of Jointed Precast Concrete Pavement Slabs

VDOT I-66 Showcase, Sept. 22, 2009
 Peter J. Smith, P.E.
 The Fort Miller Co., Inc.





Michigan Method (Michigan State University & FHWA)



Cutting Slots
 Sand Blasting Slots
 Placing
 Slots Ready to Fill

Roman Road System

Thomas Montalbino
 Roman Stone Construction Company
 631-667-0566
 tmontalbino@romanstoneco.com








Illinois State Toll Highway (ISTHA) Precast Pavement System

Illinois State Toll Highway Authority
 Stephen Gillen
 (630) 241-6800
 sgillen@getipass.com



Super-Slab® "Slab-on-Grade System"




Implementation by Agency

AGENCY	UNIFORMED INTERMITTENT REPAIR PROJECTS	REPAIR PROJECTS	SQ. YD.	UNIT TYPE
NY TOLLWAY	20	20	100,000	CONCRETE
ILLINOIS	1,500	1,500	100,000	CONCRETE
MICHIGAN	1,000	1,000	100,000	CONCRETE
MICHIGAN DOT	1,000	1,000	100,000	CONCRETE
INDIANA	1,000	1,000	100,000	CONCRETE
INDIANA DOT	1,000	1,000	100,000	CONCRETE
MINNESOTA	1,000	1,000	100,000	CONCRETE
MINNESOTA DOT	1,000	1,000	100,000	CONCRETE
MISSISSIPPI	1,000	1,000	100,000	CONCRETE
MISSISSIPPI DOT	1,000	1,000	100,000	CONCRETE
MISSOURI	1,000	1,000	100,000	CONCRETE
MISSOURI DOT	1,000	1,000	100,000	CONCRETE
NEBRASKA	1,000	1,000	100,000	CONCRETE
NEBRASKA DOT	1,000	1,000	100,000	CONCRETE
NEVADA	1,000	1,000	100,000	CONCRETE
NEVADA DOT	1,000	1,000	100,000	CONCRETE
NEW YORK	1,000	1,000	100,000	CONCRETE
NEW YORK DOT	1,000	1,000	100,000	CONCRETE
OHIO	1,000	1,000	100,000	CONCRETE
OHIO DOT	1,000	1,000	100,000	CONCRETE
OKLAHOMA	1,000	1,000	100,000	CONCRETE
OKLAHOMA DOT	1,000	1,000	100,000	CONCRETE
OREGON	1,000	1,000	100,000	CONCRETE
OREGON DOT	1,000	1,000	100,000	CONCRETE
PENNSYLVANIA	1,000	1,000	100,000	CONCRETE
PENNSYLVANIA DOT	1,000	1,000	100,000	CONCRETE
RHODE ISLAND	1,000	1,000	100,000	CONCRETE
RHODE ISLAND DOT	1,000	1,000	100,000	CONCRETE
TENNESSEE	1,000	1,000	100,000	CONCRETE
TENNESSEE DOT	1,000	1,000	100,000	CONCRETE
TEXAS	1,000	1,000	100,000	CONCRETE
TOTALS	14,800	14,800	1,480,000	CONCRETE

Toll Plaza, Tarrytown, NY

This (3,000 SF Per Eight Hour Shift) **While Maintaining** **This** (135,000 Vehicles per Day)

(Within ± 3 mm) In 2001 and 2002



Intersections

Rotterdam, NY - 2006

Brooklyn, NY - 2009

Complex Geometry

Replacing Existing Full Depth Asphalt

Bridge Approach Slabs – Iowa & NY

Denver, Iowa (2008)

Binghamton, NY (2009)

Iowa DOT

NY State DOT

Airport Taxiways

LaGuardia - 2002

Dulles - 2002

Weekend Installation

Overnight Installation

Mainline I-15 Ontario, CA (2010)

Installing Test Slabs

Tested 1.5 Years

4.3 Million Cycles

200,000 VPD
(719 Slabs – 13, 150 SY – 2010 Construction)

Installed Costs (What We Know So Far)

- Intermittent Repair Slabs
 - About \$ 432 to \$ 585 per SY
 - Similar to cost for rapid-set concrete (in some states)
- Continuous Installations
 - About \$ 350 to \$ 401 per SY
 - Tend to be up to 20% less than intermittent repair slabs
- Varies greatly with
 - Length of work window
 - Size of project
 - Local labor rates

Average Bid Prices

Project	Type of Project	Bid Date	Pavement Thickness (in)	Project Quantity (sf)	Precast Bid Price per SY	Removal Bid Price per SY	Fine Grade Bid Price per SY	Total Price per SY
I-95 New England Thruway	Production		9.99	71,956	\$382.28	\$66.89	\$35.12	\$484.29
Nassau-Queens (Long Island)	Production	Mar-08	8.85	252,784	\$376.26	\$125.42	\$18.72	\$518.40
Route 21 Newark, NJ	Production	Jan-08	8.75	44,100	\$472.50	Included	Included	\$472.50
I-280 Newark, NJ	Production	Apr-08	8.75	35,237	\$657.00	Included	Included	\$657.00
I-15 Ontario, CA	Production	Dec-09	8.00	118,404	\$349.50	Included	Included	\$349.48
NJDOT Route 130 (SB)	Production	Jun-09	8.75	2,106	\$496.00	Included	Included	\$496.00
I-15, Ogden, Utah	Production	Feb-09	8.75	27,000	\$435.48	Included	Included	\$435.48
VDOT I-66	Production	Apr-09	8.75	42,204	\$350.00	Included	Included	\$350.00
PennDOT I-676	Production	May-09	12.00	5,699	\$505.00	Included	Included	\$505.00
				Avg.	\$447.11		Wtg. Avg.	\$474.24

Trends in Developing Specifications

- Product-specific specifications still used
 - Allow the owner maximum control
 - Mobilizes System Designer's expertise and support
- More states are developing generic specifications
 - Based upon a systems approach
 - Requires proven fabrication and installation details
 - Requires proof of performance of each system
 - Allows all systems to participate
- Some states desire to develop "standard" systems
 - Risky to make a "standard" before details are proven
 - Proof of performance should still be required

Trends in Acceptance and Implementation

- A few states are fully convinced
 - Evidenced by multiple projects
- Several states have tried the concept
 - Some are planning future projects
- Most contractors embrace the concept
 - Some (in Midwest) do not!







Summary






- Jointed precast pavement slabs now in 11 states
 - Plus two Canadian Provinces
- Jointed slabs used successfully in a multiple of applications
- Contractors are becoming more proficient at installation
- Fabricators prove capable of making accurate slabs
 - In three dimensions
- Jointed precast pavements are performing
 - Some in place over 8 years

Keys to Success (Still More to Learn)

Good engineering
Open minds
Real partnering







Overview

- ◆ **PPCP Description**
- ◆ **Benefits**
- ◆ **FHWA Demonstration Projects**
- ◆ **Demonstration Project Outcomes**

Benefits

- ◆ Benefits of *Prestressed* Precast Concrete
 - Reduces/eliminates slab cracking (maintenance)
 - Reduced number of joints (maintenance/smoothness)
 - Reduced Slab Thickness (8" vs. 12")
 - Material savings
 - Allows for replacement of pavement in-kind
 - Ability to span voids/unsound support layers
 - Proven Long-Term Performance
 - 6" CIP post-tensioned pavement constructed in 1985 (near West, Texas)
 - Virtually no maintenance in 24 years

Overview

- ◆ **PPCP Description**
- ◆ **Benefits**
- ◆ FHWA Demonstration Projects
- ◆ **Demonstration Project Outcomes**

Texas Demonstration Project

- ◆ Completed 2002
- ◆ 2,300 ft of frontage road pavement along Interstate 35 just north of Georgetown, Texas.
- ◆ Full-width (36 ft x 10 ft) AND Partial-width (16 ft + 20 ft x 10 m) panels
- ◆ 8" thick precast panels
- ◆ Panels installed over 2" HMA leveling course
- ◆ 339 panels total



California Demonstration Project

- ◆ Completed 2004
- ◆ Widening of Interstate 10 near El Monte, CA
 - 27 ft traffic lanes + 10 ft shoulder
- ◆ Night construction
- ◆ Precast Panel Dimensions
 - 37 ft long x 8 ft wide, 10" - 13.1" thick
- ◆ 248 ft total project length (2 sections @ 124 ft)
- ◆ Panels installed over lean concrete base
- ◆ 31 Panels total



Missouri Demonstration Project


- ◆ Completed 2005
- ◆ Replacement of 40+ yr. old Interstate JRCP
- ◆ 1,010 ft total length (4 sections @ 250 ft)
 - 2 lanes plus shoulders: 38 ft wide
 - Pavement crown incorporated into panels
- ◆ Installed over permeable asphalt-stabilized base
- ◆ End Stressing for Post-Tensioning
- ◆ Panels: 10 ft x 38 ft x Variable thickness
- ◆ 101 panels total




Iowa Demonstration Project

- ◆ Completed 2006
- ◆ Precast Prestressed Bridge Approach Slabs
 - 77 ft at either end of a skewed bridge (16 panels)
 - Tied to an integral bridge abutment
- ◆ 2-way Post-Tensioning
- ◆ Partial-width panels (lane-by-lane construction)
- ◆ Installed over crushed limestone base
- ◆ Panels: 14 ft x 20 ft x 12 in.
- ◆ 16 panels total

Iowa Demonstration Project






Delaware Demonstration Project

- ◆ Completed July 2009
- ◆ Replacement of ASR-affected JCP
- ◆ Left turn and right turn/thru lanes at approach to intersection
 - Single lane (12') PPCP and double lane (24') PPCP
- ◆ Night construction only (7:30pm – 5:30am)
- ◆ Installed over pervious concrete base
- ◆ Panels: 10' x 12' and 24' ft x 8 in.
- ◆ Threaded P-T bars used for temporary P-T during construction (and as final tendons)
- ◆ 130 panels total

Delaware Demonstration Project



Other Projects: Red Dog Mine, Alaska (2002)



Overview

- ◆ PPCP Description
- ◆ Benefits
- ◆ FHWA Demonstration Projects
- ◆ Demonstration Project Outcomes



What Has Been Demonstrated?

- ◆ Feasibility of PPCP Construction
 - Full-width construction
 - Partial-width (lane by lane) construction
- ◆ Night Construction
 - Opening to traffic each day



What Has Been Demonstrated?

- ◆ Use of various bases
 - Hot-mix asphalt
 - Lean concrete
 - Crushed aggregate
 - Pervious concrete



What Has Been Demonstrated?

- ◆ Use of prestressing for precast pavement
 - Combination of pretensioning/post-tensioning
 - 2-way post-tensioning
 - Threaded bars for temporary P-T



What Has Been Demonstrated?

- ◆ Variable cross-slope



What Has Been Demonstrated?

- ◆ Construction on horizontal and vertical curves



What Has Been Demonstrated?


- ◆ Various expansion joints



Potential Future Applications

- ◆ Potential FHWA Demonstration Projects
 - 1) Weigh-in-Motion Installations
 - 2) Intersections
 - 3) Unbonded Overlays
 - 4) Temporary Pavement/Crossovers
 - 5) Thinner pavement sections beneath bridges
- Others.....

FHWA is providing design and construction support for demonstration projects.





I-66 Highways for LIFE Showcase
Fairfax, Virginia

Karen L. Consiglio, P.E.
Area Construction Engineer

David P. Shiells, P.E.
District Materials Engineer



September 22, 2009

I-66 Highways for LIFE

Existing Pavement Structure




- 9" JRCP built in early 1960s
- 6" of plain aggregate sub-base
- 6" cement stabilized sub-grade
- Lot of joint problems and mid-slab spalling

I-66 Highways for LIFE

Site Selection

- Based upon condition of pavement
- Available working space (barriers, drainage inlets, etc.)
- Overhead clearances
- Utilities (loop detectors, etc.)
- Curved sections

Ramp: Pre-cast Concrete Panels and Cast-in-Place Patches

7

Ramp: Right Lane to be Replaced with Pre-cast Concrete Panels

8

Highways for LIFE: Area B

I-66 Mainline Westbound

- All four lanes (including right auxiliary shoulder) to be replaced with pre-cast, pre-stressed concrete panels
- Existing concrete thickness ranges from 9" to 11"

9

I-66 Mainline: Pre-cast, Pre-stressed Concrete Panels (PPCP)

10

I-66 Mainline: Pre-cast, Pre-stressed Concrete Panels (PPCP)

11

I-66 Mainline: Pre-cast, Pre-stressed Concrete Panels (PPCP)

Panel No.	Panel Length (ft)	Panel Type	Notes
1	100.00	Anchor	Anchor Panel (AP-1)
2	100.00	Beam Panel	Beam Panel (BP-1)
3	100.00	Beam Panel	Beam Panel (BP-2)
4	100.00	Beam Panel	Beam Panel (BP-3)
5	100.00	Beam Panel	Beam Panel (BP-4)
6	100.00	Beam Panel	Beam Panel (BP-5)
7	100.00	Beam Panel	Beam Panel (BP-6)
8	100.00	Beam Panel	Beam Panel (BP-7)
9	100.00	Beam Panel	Beam Panel (BP-8)
10	100.00	Beam Panel	Beam Panel (BP-9)
11	100.00	Beam Panel	Beam Panel (BP-10)
12	100.00	Beam Panel	Beam Panel (BP-11)
13	100.00	Beam Panel	Beam Panel (BP-12)
14	100.00	Beam Panel	Beam Panel (BP-13)
15	100.00	Beam Panel	Beam Panel (BP-14)
16	100.00	Beam Panel	Beam Panel (BP-15)
17	100.00	Beam Panel	Beam Panel (BP-16)
18	100.00	Beam Panel	Beam Panel (BP-17)
19	100.00	Beam Panel	Beam Panel (BP-18)
20	100.00	Beam Panel	Beam Panel (BP-19)
21	100.00	Beam Panel	Beam Panel (BP-20)
22	100.00	Beam Panel	Beam Panel (BP-21)
23	100.00	Beam Panel	Beam Panel (BP-22)
24	100.00	Beam Panel	Beam Panel (BP-23)
25	100.00	Beam Panel	Beam Panel (BP-24)
26	100.00	Beam Panel	Beam Panel (BP-25)
27	100.00	Beam Panel	Beam Panel (BP-26)
28	100.00	Beam Panel	Beam Panel (BP-27)
29	100.00	Beam Panel	Beam Panel (BP-28)
30	100.00	Beam Panel	Beam Panel (BP-29)
31	100.00	Beam Panel	Beam Panel (BP-30)
32	100.00	Beam Panel	Beam Panel (BP-31)
33	100.00	Beam Panel	Beam Panel (BP-32)
34	100.00	Beam Panel	Beam Panel (BP-33)
35	100.00	Beam Panel	Beam Panel (BP-34)
36	100.00	Beam Panel	Beam Panel (BP-35)
37	100.00	Beam Panel	Beam Panel (BP-36)
38	100.00	Beam Panel	Beam Panel (BP-37)
39	100.00	Beam Panel	Beam Panel (BP-38)
40	100.00	Beam Panel	Beam Panel (BP-39)
41	100.00	Beam Panel	Beam Panel (BP-40)
42	100.00	Beam Panel	Beam Panel (BP-41)
43	100.00	Beam Panel	Beam Panel (BP-42)
44	100.00	Beam Panel	Beam Panel (BP-43)
45	100.00	Beam Panel	Beam Panel (BP-44)
46	100.00	Beam Panel	Beam Panel (BP-45)
47	100.00	Beam Panel	Beam Panel (BP-46)
48	100.00	Beam Panel	Beam Panel (BP-47)
49	100.00	Beam Panel	Beam Panel (BP-48)
50	100.00	Beam Panel	Beam Panel (BP-49)
51	100.00	Beam Panel	Beam Panel (BP-50)
52	100.00	Beam Panel	Beam Panel (BP-51)
53	100.00	Beam Panel	Beam Panel (BP-52)
54	100.00	Beam Panel	Beam Panel (BP-53)
55	100.00	Beam Panel	Beam Panel (BP-54)
56	100.00	Beam Panel	Beam Panel (BP-55)
57	100.00	Beam Panel	Beam Panel (BP-56)
58	100.00	Beam Panel	Beam Panel (BP-57)
59	100.00	Beam Panel	Beam Panel (BP-58)
60	100.00	Beam Panel	Beam Panel (BP-59)
61	100.00	Beam Panel	Beam Panel (BP-60)
62	100.00	Beam Panel	Beam Panel (BP-61)
63	100.00	Beam Panel	Beam Panel (BP-62)
64	100.00	Beam Panel	Beam Panel (BP-63)
65	100.00	Beam Panel	Beam Panel (BP-64)
66	100.00	Beam Panel	Beam Panel (BP-65)
67	100.00	Beam Panel	Beam Panel (BP-66)
68	100.00	Beam Panel	Beam Panel (BP-67)
69	100.00	Beam Panel	Beam Panel (BP-68)
70	100.00	Beam Panel	Beam Panel (BP-69)
71	100.00	Beam Panel	Beam Panel (BP-70)
72	100.00	Beam Panel	Beam Panel (BP-71)
73	100.00	Beam Panel	Beam Panel (BP-72)
74	100.00	Beam Panel	Beam Panel (BP-73)
75	100.00	Beam Panel	Beam Panel (BP-74)
76	100.00	Beam Panel	Beam Panel (BP-75)
77	100.00	Beam Panel	Beam Panel (BP-76)
78	100.00	Beam Panel	Beam Panel (BP-77)
79	100.00	Beam Panel	Beam Panel (BP-78)
80	100.00	Beam Panel	Beam Panel (BP-79)
81	100.00	Beam Panel	Beam Panel (BP-80)
82	100.00	Beam Panel	Beam Panel (BP-81)
83	100.00	Beam Panel	Beam Panel (BP-82)
84	100.00	Beam Panel	Beam Panel (BP-83)
85	100.00	Beam Panel	Beam Panel (BP-84)
86	100.00	Beam Panel	Beam Panel (BP-85)
87	100.00	Beam Panel	Beam Panel (BP-86)
88	100.00	Beam Panel	Beam Panel (BP-87)
89	100.00	Beam Panel	Beam Panel (BP-88)
90	100.00	Beam Panel	Beam Panel (BP-89)
91	100.00	Beam Panel	Beam Panel (BP-90)
92	100.00	Beam Panel	Beam Panel (BP-91)
93	100.00	Beam Panel	Beam Panel (BP-92)
94	100.00	Beam Panel	Beam Panel (BP-93)
95	100.00	Beam Panel	Beam Panel (BP-94)
96	100.00	Beam Panel	Beam Panel (BP-95)
97	100.00	Beam Panel	Beam Panel (BP-96)
98	100.00	Beam Panel	Beam Panel (BP-97)
99	100.00	Beam Panel	Beam Panel (BP-98)
100	100.00	Beam Panel	Beam Panel (BP-99)
101	100.00	Beam Panel	Beam Panel (BP-100)

12

VDOT

I-66 Mainline: Pre-cast, Pre-stressed Concrete Panels (PPCP)

13

VDOT

Proprietary PCP Systems: Super Slab® System

Grout ports

Photo source: The Fort Miller Company

14

VDOT

Project Challenges and Solutions

Challenges

- Differing thicknesses of ex. concrete along mainline (transverse)
- Proprietary PCP systems
- Smoothness of final pavement surface
- Estimating costs and fitting to available funding

Solutions

- Cost for #10 coarse aggregate included in PPCP bid item
- Special provisions for PPCP and PCP (based on AASHTO TIG); approved list for PCP systems; trial installation required prior to production; FWD testing for 80% joint load transfer efficiency
- Diamond grinding included for all PPCP and PCP panels (+ 50' run-on and run-off); ride-ability specification (no incentives or disincentives)
- Innovative bidding

15

VDOT

Bid Results

Section	Lane Construction	Fort Myer	General Excavation
0001	All	All	All
0002	All	All	All
0003	All	All	All
0004	3,140 SY	2,100 SY	1,373 SY
Total	\$4.97 M	\$5.00 M	\$4.99 M

CIP (9") - \$225/sy
 PCP (9") - \$350/sy
 PPCP (8") - \$410/sy

16

VDOT

Maintenance of Traffic

Extremely High Traffic Volumes

- ADT₂₀₀₈ = 184,000 vpd (5% trucks)
- Shoulder use 5:30 am to 11 am EB; 2 pm to 8 pm WB







17







VDOT

Maintenance of Traffic

Hourly Traffic Volumes

18





VDOT

Lessons Learned

Lead Time for Shop Drawings/Submittals/Trial Installations

- Specify *off-site* prior to construction

Staging Area

- Critical for deliveries, etc.

Trial Installations

- Specify *off-site* prior to construction
- Trial batches for grouts (hardware and underlab)
- Falling weight deflectometer testing;cores

Closure Pour

- Necessary for PPCP

Existing Conditions are Variable !

- Variability of existing pavements (cast-in-place)
- Tolerances for pre-casting
- Difficult to predict; especially at tie-ins

31

VDOT

Project Goals


Comparison of Technologies (CIP, PCP, PPCP)

- Costs
- Construction issues
- Availability of systems/qualified contractors
- Proprietary issues
- Time (design, shop drawings, casting, construction)
- MOT requirements
- Inspection requirements
- Long term performance

32

VDOT

Questions ?



33



I-66 Concrete Paving Repairs –Precast and Prestressed Panels Demonstration Project

Project Status

Project Overview

- Project Consists of:
 - 520 SY of Cast In Place Concrete
 - 5,780 SY of Prestressed Post Tensioned Panels
 - 4,690 SY of Precast Concrete Panels
- Current Status:
 - Cast In Place Concrete has been completed
 - 50% of the Prestressed Panels are completed
 - 45% of the Precast Panels are completed

What's Happening Now

- Overview of tonight's site visit
 - Two work areas
 - I-66 WB - Prestressed Panels
 - I-66 WB to Rte. 50 WB Ramp – Precast Panels

I-66 WB – Prestressed Post Tensioned Precast Concrete Panels

- Work in this area:
 - Post Tensioning of Panels
 - Post Tensioning Duct Grouting
 - Underslab Grouting
 - Misc. Support Operations

I-66 WB to Rte 50 WB Off Ramp – Precast Concrete Panels

- Work in this area:
 - Removal of Existing Concrete Panels
 - Drilling & Installation of Longitudinal Tiebars
 - Installation & Grading of Stone Dust Subbase
 - Installation of Concrete Panels
 - Dowel & Underslab Grouting
 - Misc. Support Operations

Why did Lane bid this project?

- We were interested in the New Technology
 - We had worked with the Fort Miller System previously @ Dulles Airport
- Good opportunity to gain experience in a potential new market of concrete paving

Considerations & Concerns @ Bid Time

- TRAFFIC
 - High Volume Roadway with limited space & access.
 - Time restriction offer a small work window.
- Schedule
 - How many panels can be placed per shift? (No historical data.)
 - How fast can panels be precast?

Considerations & Concerns @ Bid Time (cont.)

- Panel Installation
 - Would existing subgrade be suitable?
 - How do we match new panels to the existing pavement?
 - What do we do if we can't get panels installed in time to open roadway to traffic?
- Precasting
 - Accuracy & Production Concerns
 - Delivery of Material
 - Location of Precaster

Questions & Answers

PROJECT SAFETY

Personal Protective Equipment (PPE)

- Long Pants, Shirts with Sleeves, Jackets, etc.
- Work Boots/Shoes – No sneakers or tennis shoes.
- Hard Hat
- Reflective Safety Vest
- Personal Items (Medications, Food, etc.)
- Hearing Protection - will be provided by Lane if requested.
- Restrooms are available on site.

Site Conditions

- Active Work Zone
- Tight area with multiple activities.
- Always be alert and stay clear of equipment.
- Night Work – Areas are illuminated however visibility is still impaired.
- Traffic is a major Hazard – Stay Alert and Stay Away
- Ask for an escort if you would like to view an activity closer up.
- Always stay clear of Panels when they are being lifted into place.
- Stay in designated area.

What You Will See Tonight

I-66 Project

Fairfax, VA

September 22, 2009

The Super-Slab™ System

A

Slab-on-Grade

System

Super-Slab® is a patented system

Super-Slab™

The Product




Features:

- High Performance Concrete
- Embedded Dowels
- Embedded Tie Bars
- Matching Inverted Dovetail Slots
- Thickness as Required
- Length and Width as Required




Bedding Grout Port

Dowel Grout Port







Transverse Dowel Connection


- Slots on the bottom Protects Grout From De-Icing Chemicals
- Mechanical Resistance to Dowel Pop-out

Bedding Grout

- To fill any voids
- Flow rate = 17 - 20 seconds
- 2 MPa in 12 hrs.



Grout Flow Test Chamber




Pumping Bedding Grout

Two Types of Slabs (and Subgrade Surfaces)

- Single Plane
- Warped Plane
- 8 3/4" thick to replace 9"
- New slabs match existing edge

The Site




Engineering

Collection of Field Data

- Collect “x”, “y”, “z” of existing surface
 - At matching longitudinal joint
 - At right hand edge of existing ramp
 - At theoretical panel points
- Data used to develop surface model
 - Profiles are smoothed out wherever possible
- New slabs are designed and fabricated to fit design surface model

Layout

- Lay out leading corners
 - Requires surveying
- Use correct lay length
 - = theoretical length of the slab + ¼”
 - Provides for ½” maximum joint width



Removal of Existing Pavement



Slab Crab Bucket Removal

Existing pavement cut previous nights

Sometimes in More Than One Piece



Precision Grading (Super-grading)

Setting Rails for Hand Operated Grader

Set Couplings Over Panel Points (to grade)

Drop Rails in Couplings

Use Pin Straight Edge to Straighten Rails

Coupling Over Panel Point

Pin Straight Edge



First Pass (1/4" high)



Compaction

Super Grading With H.O.G.

Three Steps



Last Pass (done)

Installing Dowels and Tie Bars



Drilling for Tie Bars
Mark Out and Drill (accurately)
to Fit Inverted Dovetail Slots




Use Proper Epoxying Technique

Placing Slabs


Prior to Placing Slabs

- Make a final grade check around edges
- Install at least shims
 - At least one at each corner of previously-placed slab
- Apply bond breaker to edges previously set
 - (requires spray can of form oil)




Checking and Trimming Edges


Depth Gage for Checking Edges
Use it to make sure slabs will fit



Edge Trimmer




Install Transverse Joint Shim
At least one per corner



Apply Bond Breaker
Spray (form oil)


Placing Slabs

- Use proper size crane
 - Do not place outrigger on slab corners!
- Rig properly
 - So all four corners hit at once
- One man in each corner
- Set slabs to leading edge marks
- Check for match
 - Correct if necessary before setting next slab



Placing Slabs

One man in each corner
Crane outrigger off pavement




Setting slabs to panel point marks

Grouting


Dowel Grout

- Required properties
 - Non-shrink, high strength, fast setting, freeze thaw durable
 - Must be pumpable
 - Must reach 2500 psi in 2 hours
- Dayton Superior HD-50
 - Standard bagged grout with our specified amount of water
- Pro-Spec
 - Use water shown on the bag


Installing Dowel Grout



Chem Grout Mixer/Pump



Filling Dowel Grout Ports




Contractor-Designed Joint Dam
(Montreal Project)

Bedding Grout


- Mixture of Cement, Water & Admixture
 - Flow rate of 17 - 20 seconds
 - Must flow into thin voids
- Reaches 2 MPa \pm in 12 hours
- Use Proper Nozzle
- Keep Holes filled

Bedding Grout

Flow Rate
17 - 22 Seconds



Proof
(keep ports full)



How About Smoothness?

- Small differences between slabs are to be expected
 - There are tolerances allowed (by necessity) in the slabs
 - There are tolerances allowed in the grading
- Super-Slab® specifies finished surfaces ± 3 mm
 - In many cases this is acceptable
- For best International Roughness Index - grind
 - Grinding is a known and accepted practice

Keys to Job Site Success (Still More to Learn)

- ***Good Training***
- ***Working Together***
- ***Real Partnering***



THE LANE
CONSTRUCTION CORPORATION
OVER 100 YEARS
A Commitment to Excellence

**I-66 Pavement Repairs
Demonstration Project**
Contractor Perspective of
Precast Panel Replacement

Presented By: Erich R. Brown, P. E.

Two Innovative Concepts

- Prestressed Post Tensioned Concrete Panels
- Precast Concrete Panels

Planning Challenges

- TRAFFIC
 - I-66 WB is a High Volume Roadway
 - Time Restrictions Limited the Amount of Production per Shift.
- Access to the Work Zone
 - Limited time did not allow for a large mobilization operation
 - Staging area for equipment and materials
 - Small work area limits work force size

Planning Challenges (cont.)

- Existing Conditions
 - Condition of existing subgrade
 - Condition of existing concrete
 - Removal of slabs without damaging subgrade
- Preparation of Subgrade to Match Existing Conditions
 - Plan alignment vs. Actual
 - What methods do we use to place subgrade matl.

Planning Challenges (cont.)

- Material Deliveries
 - Staging vs. Timing delivery of Panels
 - Storage & transport of Misc. Material
- Weather
 - What happens if it starts to rain?

Strategies (and did they work?)

- TRAFFIC
 - Procurement of appropriate materials
 - Practice MOT Prior to beginning work
- Access to the Work Zone
 - Set up to use self mobilizing equipment which was staged at a nearby off site location
 - Kept crew size to a minimum – prevented crowding of work zone
 - Performed as many operations ahead of time as possible (Saw Cutting, Drilling for Slab Removal, ect.)



Strategies (cont.)

- Existing Conditions
 - Condition of subgrade was Good
 - Had it been poor – undercutting would have severely impacted production
 - Existing concrete removal performed with a rubber tired excavator w/ slab bucket attachment
- Preparation of Subgrade to Match Existing Conditions
 - Asbuilts of both work areas were taken
 - This was required for the Precast Panel Design
 - This was convenient for the Prestressed Panel Installation

Strategies (cont.)

- Preparation of Subgrade to Match Existing Conditions (cont.)
 - Methods used for Grading
 - Hand Operated Grader (HOG) (Precast Panels)
 - Laser Screed (Prestressed Panels)
 - Straight Edge (Prestressed Panels)
- Material Deliveries
 - Panel Delivery
 - Prestressed Panels were delivered directly to the work zone
 - Precast Panels were staged and brought out at night
 - Other misc. material was staged off site and brought out as needed



Strategies (cont.)





- Weather
 - If we have a hole in the ground and it starts to rain we keep going.


Construction Issues & Lessons Learned

- There is a difference between plan grades and existing grades.
 - In order to open this to traffic after each shift you have to match existing conditions.
- It takes constant effort and accurate precasting to maintain Prestressed Panel alignment.
- Existing concrete may not be in suitable condition to tie into.
- There is a method for laying out the Precast Panel Longitudinal Tiebars.

Construction Issues & Lessons Learned (cont.)

- Precasting Accuracy is a must for proper post tensioning duct alignment as well as panel alignment.
- Make sure to leave yourself room between existing and new pavement for temporary post tensioning at the end of each shift.
- Prestressed panels tend to grow.
- Post Tensioning Ducts leak when grouted.





Facts & Figures

- Prestressed Panels
 - Overall work window of 8hrs on I-66
 - 2hrs for traffic (1hr on either end)
 - Total of a 6hr work window
 - Actual Peak Production in a 6hr window
 - 12ea 10' x 12' Panels
 - Equals 120 Lane Feet or 160 SY of surface area

Facts & Figures (cont.)

- Precast Panels
 - Overall work window of 7hrs on Off Ramp
 - 1hr for traffic (1/2hr on either end)
 - Total of a 6hr work window
 - Actual Peak Production in a 6hr window
 - 12ea 16' x 12' Panels
 - Equals 192 Lane Feet or 256 SY of surface area

Facts & Figures (cont.)

- Cast In Place
 - Overall work window of 8hrs on Off Ramp
 - 2hr for traffic (1hr on either end)
 - Total of a 6hr work window
 - Actual Peak Production in a 6hr window
 - Allow 3-4 hrs for Cure Time
 - 40 Lane Feet or 53 SY of surface area

Questions?

HIGHWAYS FOR LIFE I-66 AND RT. 50 CHANTILLY, VA

By : **Carla A. Ramo**
Mid-Atlantic BD Manager



HIGHWAYS FOR LIFE...

- First Part of the Work → Casting Yard
 - Coordinate with Smith Midland the delivery and placement of the post-tensioning embedded parts.



HIGHWAYS FOR LIFE...

- Challenges :
 - Get deliveries on time to avoid delaying casting of panels. Fast paced project. No delays allowed.
 - Risky - By the time of ordering the material:
 - No contract signed
 - No approved drawings
 - Conditional Letter of Intent
 - Coordinate with Precaster to ensure proper installation of PT embedded items.



HIGHWAYS FOR LIFE...

- Scope of Work – Main Lane
 - “Temporary” Post-Tensioning Bar Tendons:
 - Installation - After Lane prepares sub-base and places friction lining and while they are moving the panels into place, Freyssinet inserts the PT bar and engages the coupler that attaches the bar to the bar in the next panel.
 - Temporary Stressing – After two consecutive panels are in place, the two bars in each panel are stressed to 18.3 Kips simultaneously with 2 each 60 ton center hole rams.



HIGHWAYS FOR LIFE...



HIGHWAYS FOR LIFE...

- Challenges – Bars were cut to 10Ft. each considering they could be slid to either end for coupling and stressing, but due to the space constraints the couplers would hang in the joints and bars would not come out far enough.
- Resolution – Added a 1Ft. Piece of bar at the first joint of each segment so that the bar would protrude enough at each joint.
- Final Stressing – After the strand tendons are placed in each segment, all bars are stressed to the permanent load of 43.9 Kips at the joint panel.



HIGHWAYS FOR LIFE...

- Permanent Post-Tensioning Strand Tendons
 - Installation - Tendon length varies from 94.33Ft. to 154.33Ft. Normally, hand pushing tendons would be achievable for these lengths.
 - Challenge #1 - Due to space constraints and misalignment at the joints, the strands would not go in manually or drill assisted.
 - Challenge # 2 - Removal of epoxy material on the area where the wedges bite strand. Causes slippage after strand is stressed.




HIGHWAYS FOR LIFE...


- Resolutions
 - Strands had to be pre-threaded and then pulled in with the use of a pick up truck.
 - More methodical epoxy stripping with the use of a stripping machine.
- Once a joint panel is reached, strands are installed and stressed to 43.9 Kips.



HIGHWAYS FOR LIFE...



HIGHWAYS FOR LIFE...



7 - Wire Strand without the coating is 0.6" in diameter !!!
THEORETICALLY, PHYSICALLY AND MATHEMATICALLY
IMPOSSIBLE!



HIGHWAYS FOR LIFE...

- Transverse Tendons
 - Installation - It was initially intended to install the entire 51Ft. of strand across the three lanes after all pavement slabs were in place.
 - Challenges - Because of the grout leaks from other operations, the ducts for the transverse tendons were getting blocked with grout.
 - Resolution - The transverse strand installation and grouting operations were divided in two. The strand for the first two lanes will be installed first from one side, and later, the wider lane will be installed from the opposite side.



HIGHWAYS FOR LIFE...

- Post-tensioning Tendon Grouting -
 - Procedure - Grout tendons (Sika Grout 300PT) from one end. Seal intermediate vents as grout travels to and out of vents toward the far end.
 - Challenges - Due to a poor seal at the joints, grout leaks into the void between and beneath the panels.
 - Resolution - No real solution in hand for the leaks. The tendon grouting became a priority to avoid a weaker cement product "invading" the space of the pt grout.



HIGHWAYS FOR LIFE...

- Ramp Super Slab
 - Dowel Grout
 - Challenges – Rapid set grout / Extra fast work pace
 - Underslab Grout
 - Challenges – Achieving manufacturer's suggested strength and fluidity.



HIGHWAYS FOR LIFE...

- Recommendations:
 - Match Casting
 - Will allow the use of couplers for better seal.
 - Cast bigger duct. Insert smaller duct with mechanical coupler for the strand.
- QUESTIONS?



HIGHWAYS FOR LIFE...

THANK YOU!





I-66 Precast/ Pre-stressed Concrete Pavement Slabs

Presented by:
Matthew I. Smith,
Vice President, Sales and Marketing
And
Jimmy Dean,
Vice President, Project Management


Challenges/ Strategies

- Aggressive Delivery Schedule
- Extremely Tight Tolerances
- Original design did not allow for proper concrete coverage.
- Keeping Conduits and Ducts clear of debris and Concrete Paste

Construction Issues and Lessons Learned

- Add 1/2" thickness to slab to fit all of the material and maintain proper coverage
- Worked extremely close with Lane Construction, VDOT and Freyssinet to ensure all details were addressed up front.
- Redesigned Panels to accommodate matching strand patterns to meet the aggressive delivery requirements.

Typical Shop Drawing








SMITH-MIDLAND[®]
EXCELLENCE IN PRECAST CONCRETE

For more information,
please contact:

Matthew I. Smith,
Vice President, Sales and Marketing
(540) 439-3266 or
MSmith@SmithMidland.com
www.SmithMidland.com

AASHTO TIG
Precast Concrete Pavement Systems
Lead State Team



VDOT Demonstration Showcase
Fairfax, VA
September 22, 2009

What is T.I.G. ?

- AASHTO's standing **T**echnology **I**mplementation **G**roup
- Group reports to the Standing Committee on Highways (Chief Engineers)
- Purpose is to "champion" the **accelerated** implementation of **proven** innovation
- Since 2000, has focused on 3-5 each year
- Uses "Lead State Team" concept


TIG Lead States Team on PCPS (8 states, 3 toll auth, 9 inds, 2 acad.)



Lead State Team members (27)

- Neeraj Buch, Ph.D.
- Thomas Kazmierowski, P.E.
- Tom Pyle
- Benjamin Timerson, P.E.
- Tommy Nantung
- Celik Ozyildirim, Ph.D., P.E.
- Donald Klugo
- Scott Murell, P.E.
- Leif Wathne, P.E.
- Shiraz Tayabji, Ph.D., P.E.
- Mark Dunn
- Mike Brinkman, P.E.
- Sam Tyson
- Tom Gemmiti
- John Donahue
- Peter Smith
- Malcolm Lee
- Timothy LaCoss, Chair
- Mark Snyder
- Brent Barron
- David Merritt, P.E.
- Peter Melewski, P.E.
- David Thomas
- Butch Marcelle
- Ernest Barenburg, Ph.D.
- Steven Gillen
- Keith Platte

PCPS Team Mission



To promote the **broader** and **accelerated** use of Precast Concrete Pavement Systems for the Repair, Rehabilitation and Reconstruction of PCC Pavements to transportation agencies and owners nationwide.

AASHTO TIG SUCCESSES

- Developed a nationally recognized forum for PCPS
- Identified various PCPS Systems, their attributes, their applications and their history.
- Developed generic specifications and guidelines for PCPS, where none existed.
- Developed relationships with ACI, PCI, NPCA, ACPA, SHRP and other national organizations and programs to help promote the deployment of PCPS
- Developed and submitted an application for the FHWA/AASHTO 2011 International Scanning Tour on PCPS Applications.
- Developed and implemented a Marketing Plan for PCPS to focus our outreach efforts and have partnered with FHWA's Highways for Life Program to further the outreach efforts nationwide

Marketing Plan for PCPS Deployment

- Develop documents for technology transfer
- Hold webinars on PCPS
- Support PCPS Demonstration Showcases



Variety of PCPS Systems?



Jointed System - Ft. Miller SuperSlab™



Prestressed Precast Concrete Pavement



Kwik Slab™



Uretex USA™



FDR/DBR

AASHTO TIG SPECIFICATIONS & GUIDELINES FOR PCPS

1. Guidance and Considerations for the **Design** of Precast Concrete Pavement Systems
2. Generic Specification for **Fabricating and Constructing** Precast Concrete Pavement Systems
3. Generic Specification for Precast Concrete Pavement System **Approval**
4. Precast Concrete Pavement Systems for Rapid Pavement Repair and Replacement: **Basic Information and Commentary**

Available at WWW.AASHTOTIG.ORG under the PCPS dropdown menu

www.aashtotig.org

What's available on-line?

- Detailed information about each of these 5 Precast Paving Systems
- Design Guideline Specifications
- Construction Guideline Specifications
- Approval Guidelines for PCP Systems
- Research Reports
- Case Histories
- Proven Agency Specifications (9 states)
- Marketing Plan for PCPS Deployment



Agency Partnerships



Contact Information

Gary L. Hoffman
Principal Engineer
Applied Research Assocs., Inc.
(717) 691-7625
ghoffman@ara.com

To find out more details about
Precast Concrete Pavements look at
WWW.AASHTOTIG.ORG




www.aashtotig.org
What's available on-line?

- Detailed information about each of these 5 leading Precast Paving Systems.
- Design Guideline Specifications
- Construction Guideline Specifications
- Approval Guidelines for PCPS
- Research Reports
- Proven Agency Specifications
- Marketing Plan to Deploy PCPS

AASHTO TIG SPECIFICATIONS & GUIDELINES FOR PCPS

1. Guidance and Considerations for the Design of Precast Concrete Pavement Systems
2. Generic Specification for Fabricating and Constructing Precast Concrete Pavement Systems
3. Generic Specification for Precast Concrete Pavement System Approval
4. Precast Concrete Pavement Systems for Rapid Pavement Repair and Replacement: Basic Information and Commentary

Available at WWW.AASHTOTIG.ORG under the PCPS dropdown menu



Paving and Pavement Rehabilitation Applications

- **Continuous Paving**
- **Intermittent Full Depth Repairs of PCC Pavements**
- **Applications: airport runways & taxiways, heavily traveled highways, ramps, toll plazas, intersections, crosswalks, ports-docks, bus pads, smart-sensor embedment's, bridge approach slabs, pavement under bridges – vertical clearance**

Snapshot of Precast Concrete Pavement Systems in the USA (2006)

- **Precast Prestressed Concrete Pavement System**
 - **Precast/Prestressed Concrete Paving System** (non-proprietary)
 - Pre-stressed/Post-tensioned Panel system
 - FHWA Sponsored (CPTP program)
- **Conventionally Jointed Precast Concrete Pavement Systems**
 - **Uretex USA System** (proprietary)
 - Precast Panels on HDP foam with 'Stitch in Time' load transfer device
 - **Kwik Slab System** (proprietary)
 - Slab on grade, full load transfer, grout bed
 - **Ft. Miller - Super-slab System** (proprietary)
 - Slab on grade with full load transfer, grout bed
 - **Michigan - Precast Full Depth Replacement/DBR** (non-proprietary)
 - Slab on flowable fill or HDP - dowels on top

Should Precast Concrete Pavement Systems be considered a threat to my business?

- PCPS provides another acceptable pavement treatment for rigid pavements
- Proven to work in shortened work windows = reduced risk
- Economically comparable to RSC/HES treatments
- Providing another alternative solution for owner-agencies to avoid and curtail the "HMA overlay" paradigm for the rehabilitation of rigid pavements






Paving and Pavement Rehabilitation Applications

- Continuous Paving
- Intermittent Full Depth Repairs of PCC Pavements
- Applications: airport runways & taxiways, heavily traveled highways, ramps, toll plazas, intersections, crosswalks, ports-docks, bus pads, smart-sensor embedment's, bridge approach slabs, pavement under bridges - vertical clearance

Benefits of PCPS

<ul style="list-style-type: none"> ■ Cast under ideal conditions ■ Long life expectancy with low maintenance ■ Placement in a short time frame - congestion & safety ■ Less Risk to owner/contractor ■ Growing documentation of performance history ■ Established industry, method and technology ■ Staged construction is possible ■ Installation not affected by adverse weather conditions 	<ul style="list-style-type: none"> ■ Supported by FHWA, AASHTO, ACPA, NPCA, PCI ■ Reduced Work Zone timeframe ■ Choice of surface Textures ■ Pre-approval of PCPS System is possible ■ Pre-existing specifications are available ■ Generic specifications are available ■ Economically competitive with alternative PCC pavement treatments
---	--

Variety of PCPS Systems?


 <p>Ft. Miller - SuperSlab™</p>	 <p>Prestressed Precast Concrete Pavement</p>	
 <p>Kwik Slab™</p>	 <p>Uretex USA™</p>	 <p>FDR/DBR</p>

PCPS Projects in 2008 & 2009

- NYSTA I-95 (CT-State line/Mamaroneck River to Cross Bronx Expressway)
- NYSDOT - Nassau-Queens Expressway, Staten Island-West shore Expressway, Approach to Alexander Hamilton Bridge
- NY City DOT- Approach to Brooklyn Bridge
- NJDOT I-280 & Rt.21 (Newark)
- Toronto, Canada (Downtown, Hwy 427)
- Iowa DOT (precast bridge approaches)
- DELDOT, intersection Rt.896 & Rt. 40 (Bear, DE) ☆
- Highways for Life Projects
 - Virginia DOT I-66 Mainline & Interchange Ramp ☆
 - Florida DOT (Daytona) - Intersections
 - CALTRANS I-15 - Mainline ☆
 - NYSDOT I-88 Bridge Approach Slabs (Central NY)

**Should Precast Concrete Pavement
Systems be considered a threat to
my business?**

- PCPS provides another acceptable pavement treatment for rigid pavements
- Proven to work in shortened work windows = reduced risk
- Economically comparable to RSC/HES treatments
- Provides another alternative solution/tool for owner-agencies




NPCA
Precast ... The Concrete Solution

Highways for LIFE PCPS Showcase
September 22-23, 2009
presented by Evan Gurley

National Precast Concrete Association (NPCA)

- International trade association founded 1965 (over 1100 members)
 - Producers (800+)
 - Associates
 - Professionals
- Promotes the use of precast and prestressed products
 - Use
 - Quality
 - Knowledge
 - Value to our members






NPCA Answers the Industry's Call

NPCA Establishes The PCPS Product Committee (6/08)

Members:

- Peter J. Smith, PE (Chairman)** – Fort Miller Co. Inc.
- Philip Burkhart (Board Liaison), Utility Concrete Products LLC
- Mike Brinkman, NYDOT
- Steve Gillen, IL State Toll Authority
- Tom Heraty, Utility Concrete Products LLC**
- Timothy LaCoss, FHWA NY Division
- Stephanie Loud, Mountain West Precast**
- Gene Martin, Torre Hill Concrete Products Inc.**
- Thomas Montalbano, Roman Stone Construction Co.**
- Martin Rohn, Durisol
- Robert Sauber, NJDOT
- Shiraz Tayabji, Fugro Consultants, Inc.
- Mark Voiselle, Jensen Precast**
- NPCA Staff




Note: **BOLD** denotes a producer member



NPCA Answers the Industry's Call


PCPS Committee Progress:

- Agreed in principle to support AASHTO-TIG Guidelines
 - Promotes quality of installation, fabrication, and design
 - Performance based specification and guidelines
- Developing PCPS web site information for producers and specifiers
 - Case studies/project profiles of completed and in-progress projects
 - PCPS Promotional/Technical Brochures
 - Developing "What Agencies Want to Know" materials
- Develop educational materials
- Continued collaboration with AASHTO-TIG




Benefits to Producers

- Sets standard of quality for all manufacturers
- Learn new ways to improve processes, efficiency, and products
- Industry self regulation starts here
- Recognition of quality conscious producers
- Marketing opportunities and support
- Levels the playing field for all producers wishing to supply products to the DOTs or other specifying agencies (product neutral)



Benefits to Agency Owners

- Industry-Wide Body of Producers to Interface With
- Partners in Developing Standards of Quality
- Resource for Producer Capabilities
- Repository for Information on Fabrication and Installation Practices
- Support for Technical and Informational Forums
- Forum for Resolving Specification and Production Issues in the Interests of Reducing Costs and Improving Quality



NPCA Plant Certification Program

- Comprehensive third party certification program
- Promotes quality
- Easily understood by plant workers
- *Process* not product focused
- Assures consistent quality throughout operation
- Revenue neutral to our members
- 370+ plants to date



NPCA Plant Certification Program

- | Precast | Prestressed |
|--|---|
| • Introduced in 1987 | • Introduced in Feb '08 in support of our members |
| • 30 State DOTs approve ...and growing | • 8 State DOTs approve (7 more pending) |
| • Accepted, proven and credible in eyes of other regulating agencies | • Third party verified as equivalent or exceeds other industry programs |
| • Cost effective: \$3450.00/yr | • Cost effective: \$12,000.00/yr (precast and or prestressed) |



NPCA

Precast ... The Concrete Solution

Thank You!

Questions?

- For additional information please contact:

Evan Gurley
Technical Services Engineer
NPCA
Phone: 800-366-7731
Email: egurley@precast.org



Precast Concrete Pavement Systems: ACPA Perspective

VDOT/Highways for LIFE Showcase
I - 66 & Route 50, Fairfax, VA
September 22 - 23, 2009



Leif Wathne

Highways for LIFE

- ACPA supportive of the program!
- 2005 resolution BOD

"American Concrete Pavement Association supports the Highways for L.I.F.E. initiative and will join FHWA in bringing the goals of the program into practice in the highway community"




Highways for LIFE

- ACPA continues to be engaged...
- Goals are consistent with ACPA's emphasis on *"long-lasting highway solutions that present as little imposition on the driving public as possible."*
- ACPA is also very supportive of research and implementation of innovative approaches to meet these goals



- Track 7 of the CP Roadmap, **High-Speed Concrete Pavement Rehabilitation & Construction**
- Subtrack 2 **Precast and Modular Pavement Systems**



Precast Pavement Systems...

- One solution to address these challenges!
- Particularly where:
 - Tight time constraints
 - Long term durability is paramount
- Off-site casting
 - Controlled environment
 - Careful quality control acceptance
 - Lower risk...



Precast Pavement Systems...



- Get in, get out, stay out!

- Another option available to the agencies



Precast Pavement Systems...

- ACPA will continue to stay engaged
- Support advancements in technology that healthy competition enables...
- Provide highway user with the
**High Quality, and
Long Lasting**
solutions they expect and deserve.

Precast Pavement Systems...

- As with any innovation... *Early Experiments
in Transportation*
there will be challenges
- ACPA is excited about
being part of bringing
this technology into
practice in the highway
community!

Questions?

lwathne@acpa.org

**Precast/Prestressed Concrete Institute
(PCI)**



**Highways for LIFE
Fairfax, Va
September 2009**

William Nickas, P.E.
Director, Transportation Systems
Precast/Prestressed Concrete Institute
Chicago, IL

Precast Concrete Pavements



Agenda

- FHWA/AASHTO and Accelerated Construction Techniques and Technologies (ACTT)**
- PCI Plant Certification**
- Cooperative Agreement with FHWA and PCI**



**FHWA - AASHTO
SCANNING PROGRAM -
2004**

**Prefabricated Bridge Elements and
Systems**



SCAN MISSION


To investigate and document the applications and experience with prefabricated bridges in Japan and selected European countries, with emphasis on:

- Routine bridges with 20 ft – 140 ft spans
- Innovative systems
- Replacement and new highway and railroad bridges
- Including seismic considerations and emergency work

TOPICS OF INTEREST

- Minimized traffic disruption (Congestion)
- Improved work zone safety
- Minimized environmental impacts
- Improved constructibility
- Improved product quality
- Lower life-cycle costs

SCAN COUNTRIES




Netherlands

Belgium

Japan

France

Germany



About PCI

- PCI is an international trade association and Technical Institute
 - Promotes technical understanding and use of high-quality precast and prestressed concrete
 - Full staff of technical and marketing specialists

Two black and white photographs of concrete bridges are shown at the bottom right of the slide.

About PCI

- Over 350 Producer Member plants
 - Architectural, structural, and specialty precast concrete products and structures
 - Every U.S. PCI Producer Member plant must be PCI Certified
 - PCI Membership is not required to be PCI Certified
 - Over 80 Technical Committees

A black and white photograph of a concrete bridge with multiple arches is shown at the bottom right of the slide.

About PCI

- Approximately 200 Supplier Associate Members
- 100 Erector Associate Members
 - PCI Qualified/Certified Erector Program
- Over 1,300 Professional Members
 - Academics, design professionals, and other industry stakeholders
 - Provide much of the technical knowledge contained in PCI design guides and other technical publications

A black and white photograph of a concrete bridge with multiple arches is shown at the bottom right of the slide.

About PCI

PCI Publications

- Design Manuals and Guidelines
- Quality Control Manual
- PCI Journal, Ascent, and Aspire Magazines

Three magazine covers are shown: 'Journal' with the headline 'CONNECTING CONCRETE', 'Ascent' with a building facade, and 'Aspire' with a bridge.

About PCI




- Codes and Standards
 - PCI works very closely with code bodies, such as ACI, ICC, ASTM, AASHTO, etc.
- Industry Events
 - PCI works with FHWA in producing the National Bridge Conference

Logos for ACI (American Concrete Institute), AASHTO (American Association of State Highway and Transportation Officials), and ASTM (American Society for Testing and Materials) are displayed.

The logo for the U.S. Department of Transportation Federal Highway Administration is shown at the bottom right.



PCI **About PCI**

- Research & Development
 - DSDM Seismic Project
 - FHWA Precast Pavement Project



PCI **About PCI**



- PCI Regional Representation
 - 11 Regional Associations Affiliated with PCI
 - Mid-Atlantic Precast Association (MAPA)




PCI **PCI Certification Programs**

PCI has 3 Different Certification Programs:

- Plant Certification Program – 1967
- Personnel Training & Certification – 1985
- Erector Qualification and Certification - 1999




PCI **PCI Plant Certification**



Program History:


- Plant Certification Program established in 1967
- Began with 36 Plants
- Voluntary membership until 1991
- Mandatory for PCI Producer Members after 1991 – PCI Membership is not required
- Approximately 300 Plants Currently Certified

PCI **PCI Plant Certification**




Purpose:

- Provide a means for project owners/specifiers to select producers who demonstrate compliance to nationally recognized standards of engineering, production and quality control
- To permit certified producers to distinguish themselves from non-compliant/non-participating producers



PCI **PCI Plant Certification**





Product Groups and Categories:

- A — Architectural Products (MNL-117)
- B — Bridge Products (MNL-116)
- C — Commercial (Structural) Products (MNL-116)
- G — Glass Fiber Reinforced Concrete (GFRC) Products (MNL-130)

PCI Plant Certification

Product Groups and Categories:


- Supplemental, Non-Prestressed, Non-Architectural Products
- MNL-118 will be released and program launched in 2009



PCI Plant Certification



Program Recognition


- AIA MASTERSPEC
- Unified Facilities Guide Specifications (UFGS)
 - A joint effort of the U.S. Army Corps of Engineers (USACE), the Naval Facilities Engineering Command (NAVFAC), the Air Force Civil Engineer Support Agency (AFCEA) and the National Aeronautics and Space Administration (NASA)
- US Department of Agriculture – FSIS



PCI Plant Certification

Program Recognition



- US Department of Transportation - Federal Aviation Agency  Federal Aviation Administration
- Federal Bureau of Prisons 
- General Services Administration (GSA)
- Federal Highway Administration  FHWA
- 31 state Departments of Transportation
- Houston, Las Vegas, Phoenix, Seattle, and Portland



PCI Plant Certification

State DOT-Specific Certification


- PCI Working with other DOTs in developing programs specifically tailored to their needs
- Auditors will provide a special report specifically addressing DOT-specified criteria
- IL DOT, TX DOT, Mass Highways



PCI Plant Certification

QC Criteria

- Detailed quality control and audit criteria
- Drawings and Calculations Reviewed
- Comprehensive Tolerance Manual
- Detailed Quality System Manual (QSM) must be approved by PCI



PCI Plant Certification

Program Oversight

- Overseen by a diverse and balanced Quality Assurance committee
 - design professionals, consultants, producers, and materials suppliers.
- Further oversight provided by PCI Technical Activities Committee



PCI Plant Certification





Audits and Auditor Qualification

- 2-day, twice per year audits
- All audits unannounced
- IAS Accredited
- Audit firm has over 40 years of experience



Conclusion

- PCI wrote the book
- PCI has 40+ year track record for precast and precast / prestressed quality control and quality assurance programs
- PCI will work to tailor the program to each states' needs



Precast Concrete Pavements

**Engaging Industry –
A Cooperative Approach**





Precast Concrete Pavements

**Precast/Prestressed Concrete Institute
(PCI)**

**Federal Highway Administration
(FHWA)**

28





Precast Concrete Pavements

PRECASTING PLANTS

A manufacturing operation...

...not off-site construction!

29




Precast Concrete Pavements

PCI-FHWA Cooperative Agreement

**“Advancement of Precast Prestressed
Concrete Pavement System
through
Technology Transfer
and
Development of Industry Guidance
for
Design and Engineering”**

30



Precast Concrete Pavements

PCI-FHWA Cooperative Agreement

This is a 4 year PROGRAM

Part A: Strategy for technology transfer

- agency/owner
- industry communities



Part B: Development of industry guidance for design and engineering



AASHTO
THE VOICE OF TRANSPORTATION




31

Precast Concrete Pavements

PCI-FHWA Cooperative Agreement

- **The Transtec Group**
 - David Merritt
 - TxDOT Demonstration Project
 - Was also involved with the CalTrans I-10 in El Monte, CA




32

Precast Concrete Pavements


PCI-FHWA Cooperative Agreement

- **Non-Proprietary**
- **Manufactured in PCI-Certified Plants**
- **“Precast Prestressed Concrete Pavements” (PPCP)**



Georgetown panel types

Joint Base (multiple) Central Stressing




33

Precast Concrete Pavements

What is PPCP?

- **Precast Prestressed Concrete Pavement**
 - “Standardized” full-depth precast panels
 - Keyed panel joints for vertical alignment during assembly (generally, not match-cast)
 - Constructed over a prepared base (HMA, LCB, Aggregate Base, etc.)




34

Precast Concrete Pavements

What is PPCP?


- 2-way prestressing
- Combination of pretensioning/post-tensioning
- Or 2-way post-tensioning
- Bonded/grouted P-T system



35

Precast Concrete Pavements


Typical PPCP Panel





Ducts for Post-tensioning

Continuous Shear Key

Pretensioning Strands



36




Precast Concrete Pavements

Benefits

WHY PRESTRESSED CONCRETE?

- Reduces/eliminates slab cracking (maintenance)
- Reduced number of joints (maintenance/smoothness)
- Reduced Slab Thickness (8" vs. 12")
 - Material savings
 - Allows for replacement of pavement in-kind
- Ability to span voids/unsound support layers
- Proven Long-Term Performance
 - 6" CIP post-tensioned pavement constructed in 1985 (near West, Texas)
 - Virtually no maintenance in 23 years

39







Precast Concrete Pavements



PCI-FHWA Cooperative Agreement



- Program Activity 1
 - Create contacts lists
 - ETG
- Program Activity 2
 - Create the "The National Center for Prestressed Concrete Highway Pavements"
 - Board of Advisors
- Program Activity 3
 - Informational Literature
- Program Activity 4
 - Showcases and workshops



42



PCI Precast Concrete Pavements	
PCI-FHWA Cooperative Agreement	
- Program Activity 5	
• Guidance Documents, Sample Plans, Specifications	
- Program Activity 6	
• PCI Pavement Committee	
– Develop "action items"	
– Develop a detailed timeline	
– Industry "guidance" documents for "design and engineering" of the PPCP System	
43 	

PCI Precast Concrete Pavements	
PCI-FHWA Cooperative Agreement	
Four "Guidance Documents"	
1) Selecting Applications for Precast Concrete pavements	
2) Design, Layout and Maintenance of Precast Concrete Pavements	
3) Precast Pavement Panel Fabrication Recommendations	
4) Construction Recommendations for Precast Concrete Pavements	
44 	

PCI Precast Concrete Pavements	
PCI-FHWA Cooperative Agreement	
Selecting Applications for Precast Concrete Pavements (Volume 1 of 4)	
• Considerations for Selection	
• Types of Applications	
• Site Selection	
• Agency Considerations	
• Resources	
• Appendix - Projects	
45 	

PCI Precast Concrete Pavements	
PCI-FHWA Cooperative Agreement	
Design, Layout and Maintenance of Precast Concrete Pavements (Vol. 2 of 4)	
• Key Features	
• Design Considerations	
• Pavement Management Considerations	
• Performance Monitoring	
• Appendix – Details and Specifications	
46 	

PCI Precast Concrete Pavements	
PCI-FHWA Cooperative Agreement	
Precast Pavement Panel Fabrication Recommendations (Vol. 3 of 4)	
• Producer Qualifications	
• Formwork	
• Materials	
• Prestressing	
• Expansion Joints	
• Concreting	
• Lifting/Handling	
• Acceptance Testing	
47 	

PCI Precast Concrete Pavements	
PCI-FHWA Cooperative Agreement	
Construction Recommendations for Precast Concrete Pavements (Vol. 4 of 4)	
• Installation-Staging	
• Base Preparation	
• Materials	
• Installation-Equipment & Methods	
• Post-Tensioning	
• Final Surface Finish	
• Final Inspection	
48 	

Precast Concrete Pavements

PCI-FHWA Cooperative Agreement

Cooperative Effort to Engage Industry and Agencies



49  

**Precast/Prestressed Concrete Institute
(PCI)**

**Highways for LIFE
Fairfax, Va
September 2009**

William Nickas, P.E.
Director, Transportation Systems
Precast/Prestressed Concrete Institute
Chicago, IL